

480 ESQUIMALT

CIVIC ADDRESS :
480 + 492 ESQUIMALT RD. VICTORIA, BC. V9A 3L1

LEGAL ADDRESS :
LOTS 3,4 + 6, PLAN 9705 and LOT B, PLAN 21975, SECTION 31, ESQUIMALT DISTRICT

DELEGATED DEVELOPMENT PERMIT SUBMISSION
OCTOBER 10th, 2025

DRAWING LIST

A0.00	COVER SHEET
A0.01	PROJECT DATA
A1.02	STATUTORY R.O.W. & SETBACKS
A1.04	SITE PLAN PROPOSED
A2.01	P1 FLOOR PLAN
A2.02	L1 FLOOR PLAN
A2.03	L2 FLOOR PLAN
A2.04	L3-6 FLOOR PLAN
A2.05	ROOF PLAN
A4.01	BUILDING SECTIONS



CLIENT

WEXFORD DEVELOPMENT
CONTACT : EMMA ROKOSH
605-11 AVE SW, SUITE 203
CALGARY, AB T2R 0E1

ARCHITECT &
PRIME CONSULTANT

DIALOG
CONTACT : VANCE HARRIS
406 - 611 ALEXANDER STREET,
VANCOUVER, BC, V6A 1E1, CA

STRUCTURAL ENGINEER

RJC
CONTACT : LEON PLETT
220 - 645 TYEE ROAD
VICTORIA, BC, V9A 6X5, CA

MECHANICAL ENGINEER

AVALON MECHANICAL
CONTACT : JAMIE CLARKE
300 - 1245 ESQUIMALT ROAD,
VICTORIA, BC, V9A 3P2, CA

ELECTRICAL ENGINEER

E2 ENGINEERING INC.
CONTACT : PATRICK LOURDU
530 HERALD STREET,
VICTORIA, BC, V8W 1S6, CA

LANDSCAPE ARCHITECT

BIOPHILIA COLLECTIVE
CONTACT : BIANCA BODLEY
1608 CAMOSUN ST,
VICTORIA, BC, V8T 3E6, CA

CIVIL ENGINEER

JE ANDERSON
CONTACT : ROSS TUCK
4212 GLANFORD AVE,
VICTORIA, BC, V8Z 4B7, CA

CODE

GHL CONSULTANTS
CONTACT : FRANKIE VICTOR
800 - 700 W PENDER STREET,
VANCOUVER, BC, V6C 1G8, CA

INTERIOR DESIGN


HOLLAND DESIGN
CONTACT : KAREN BLACKWOOD
1480 - 400 3RD AVE SW,
CALGARY, AB, T2P 4H2, CA

ENVELOPE

MORRISON HERSHFELD
CONTACT : JASON MCKENZIE
2ND FLOOR, 536 BROUGHTON ST
VICTORIA, BC, V8W 1C6, CA

Revisions
Bubbled areas indicate revisions compared to the previously submitted plans.

Received Date
October 15, 2025



PROJECT INFORMATION SHEET		
CIVIC ADDRESS	480 + 492 ESQUIMALT ROAD, VICTORIA, BC, V9A 3L1	
LEGAL ADDRESS	LOTS 3 & 4, PLAN 9705 and LOT B, PLAN 21975. ALL OF SECTION 31 ESQUIMALT DISTRICT	
SITE INFORMATION	PERMITTED / REQUIRED	PROPOSED
ZONING	M2-E	M2-E
USE	LIGHT INDUSTRIAL	MULTI-USE
	HIGH TECH	WORK-LIVE
	WORK-LIVE	CAFÉ / RESTAURANT
	SERVICE-COMMERCIAL	RETAIL
	LIMITED RETAIL	OFFICE
PROPERTY AREA (sq.m)	2,197.82	
NET DEVELOPABLE AREA (sq.m) AFTER SRW	2,063.64	
TOTAL FLOOR AREA (sq.m)	6,593.46	6,582.51
FLOOR SPACE RATIO	3.00	3.00
COMMERCIAL FLOOR AREA - GROSS (sq.m)		222.90
COMMERCIAL FSR	1.4 MAX	0.10
RETAIL SPECIFIC FSR		0.05
MEZZANINE AREA (sq.m)	28.50%	0.0%
LIVE-WORK UNIT AREA - GROSS (sq.m)		508.49
RESIDENTIAL FLOOR AREA - GROSS (sq.m)		5,851.12
SITE COVERAGE (%)		64.7%
OPEN SITE SPACE (%)		35.3%
BUILDING HEIGHT (AV. GRADE TO TOP OF ROOF)	20m MAX (OCP) 15m MAX (ZONING) 4m MAX (within 7.5m of RES ZONING)	20.10m
BUILDING HEIGHT (AV. GRADE TO TOP OF STAIR ROOF) *DOES NOT INCLUDE ELEV. OVERRUN		23.20m
NUMBER OF STOREYS (PER BCBC)	6	6
PARKING STALLS (NUMBER) ON SITE	113	39
BICYCLE PARKING NUMBER (CLASS 1 AND CLASS 2)	CLASS 1 - 113 / CLASS 2 - 13	CLASS 1 - 142 / CLASS 2 - 24
BUILDING SETBACKS (m)		
NORTH YARD (M-1 ADJACENCY)	No Required Setback	7.04-7.27 at L1, 9.39-9.62m above L2
NORTH YARD (R3-2 ADJACENCY)	3m at Residential Properties	2.3-4.0m at L1, 3.92m above L2
SOUTH YARD	No Required Setback	2.65-4.07m at L1, 4.23-4.13m above L2
WEST YARD	No Required Setback	3.91m
EAST YARD	No Required Setback	4.08m
STREET CORNER (up to 3m)	3m Diagonal at Street Corner	8m x 8m Diagonal
RESIDENTIAL USE DETAILS		
TOTAL NUMBER OF UNITS		95
MINIMUM UNIT FLOOR AREA (sq-m)		32.07sm / 350 sf

VEHICLE PARKING CALCULATION				
RESIDENTIAL PARKING			CURRENT	
Unit Sizes	Number of Units	Parking Factor	Stalls Required	Provided
Less than 45m² (484 sf)	27	0.75	20.3	
BTW 45m² & 70m² (485-753 sf)	34	0.9	30.6	
Greater than 70m² (754 sf)	34	1.3	44.2	
Total Residential	95		95	25
Visitor Stalls	95	0.1	10	4
Total			105	29
COMMERCIAL PARKING				
Unit Type	Unit Area	Parking Factor	(sm)	Stalls Required
UNIT 01 - Level 01 Indoor - Café	122.7	1	20	6.1
UNIT 01 - Level 01 Outdoor - Café	45.8	1	20	2.3
Total Unit 01				8.4
UNIT 02- Level 01 East - Retail	100.2	1	37.5	2.7
Total Unit 02				2.7
Total Commercial Stalls				11
				8*
				* Shared Commercial / Visitor Stalls
Dedicated Car Share Stall (3m x 5.5m)				2
Total Spaces Required				116
				39
Difference :				77
				34% of Required
COMMERCIAL LOADING				
Off Street Loading (4m x 9m)				1
				1

BUILDING CODE SUMMARY		
REFERENCE CODE	BCBC 2018 PART 3	
CLASSIFICATION	3.2.2.50 GROUP C, UP TO 6 STOREYS, SPRINKLERED 3.2.2.58 GROUP D, UP TO 6 STOREYS, SPRINKLERED 3.2.2.15 STOREYS BELOW GROUND	
NUMBER OF STREETS	FACING TWO STREETS	
SPRINKLERED	YES	
EMERGENCY POWER	YES	
FLOOR ASSEMBLY FIRE RATING	1 HR (2 HR PARKING)	
MEZZANINE FIRE RATING	1HR	
ROOF FIRE RATING	1HR	
CONSTRUCTION	PERMITTED	PROPOSED
	NONCOMBUSTIBLE CONS.	NC CONS. P2-L2
	COMBUSTIBLE CONSTRUCTION	C CONS. L2-ROOF
BUILDING AREA	1,500 sm	1,422.61 sm
BUILDING HEIGHT	6 STOREYS	6 STOREYS (Above Grade) 1 STOREY (Below Grade)
OCCUPANCY	C - RESIDENTIAL A-2 - ASSEMBLY E - RETAIL D - OFFICE F-3 - PARKING	C - RESIDENTIAL A-2 - ASSEMBLY E - RETAIL D - OFFICE F-3 - PARKING

RESIDENTIAL BIKE STALL REQUIREMENTS				
		Long Term		Short Term
Size of units	# of Units	Bike Stall Factor	Required	Required
Units Below 45m² (484 sf)	27	1	27	
Units Above 45m² (485 sf)	68	1.25	85	
Short Term - 6 per building or	95	0.1		10
Total Required Residential Stalls			112	10
Total Provided Residential Stalls			134	12

RESIDENTIAL BIKE STALL BREAKDOWN				
		Min / Max	Required	Provided
Ground mounted horizontal stalls	(Min. 1/3 of required)		37.3	38
Oversize cargo stalls	(Min. 10% of required)		11.2	12
Stacked Stalls (Based on Dero Decker)				40
Vertical Stalls				44

COMMERCIAL BIKE STALL REQUIREMENTS						
Unit Type	Unit Area	Bike Stall Factor	Long Term		Short Term	
			(sm)	Required	(sm)	Required
UNIT 01 - Level 01 Indoor - Café	122.7	1	400	0.3	100	1.2
UNIT 01 - Level 01 Outdoor - Café	45.8	1	400	0.1	100	0.5
Total Unit 01				0.4		1.7
UNIT 02 - Level 01 East - Retail	100.2	1	200	0.5	200	0.5
Total Unit 02				0.5		0.5
Total Required Commercial Stalls				0.9		2.2
Total Provided Commercial Stalls				8		12

480 ESQUIMALT FSR AREAS			
	FLOOR AREA (sm)	FLOOR AREA (sf)	FSR
COMMERCIAL 01 - CAFE	122.7	1,321	
COMMERCIAL 02 - RETAIL	100.2	1,079	
COMMERCIAL SUBTOTAL	222.90	2,399	0.10
LIVE-WORK UNITS	508.49	5,473	
LIVE-WORK SUBTOTAL	508.49	5,473	0.23
RES CIRCULATION A	342.08	3,682	
RES LOBBY A	43.44	468	
RES M/E A	32.06	345	
RES UNITS A	2,382.26	25,642	
RES BLDG A SUBTOTAL	2,799.84	30,137	
RES CIRCULATION B	354.36	3,814	
RES LOBBY B	22.35	241	
RES M/E B	17.6	189	
RES UNITS B	2,603.60	28,025	
STORAGE / MISC.	53.37	574	
RES BLDG B SUBTOTAL	3,051.28	32,844	
RESIDENTIAL SUBTOTAL	5,851.12	62,981	2.66
BUILDING TOTAL	6,582.51	70,853	3.00
SITE AREA	2,197.82	23,657	

*FSR AREAS DO NOT INCLUDE ELEVATOR SHAFTS, BICYCLE STORAGE ROOMS, OR ANY AREA BELOW LEVEL 1. AREAS ARE CALCULATED TO INSIDE FACE OF EXTERIOR WALLS.

RESIDENTIAL UNIT BREAKDOWN			
TYPE	SIZE RANGE (sf)	QUANTITY	PERCENTAGE
LIVE-WORK	360-690	10	10.5%
STUDIO	370	10	10.5%
1 BEDROOM	450-550	41	43.2%
2 BEDROOM	800-900	20	21.1%
2 BED + DEN	920-940	9	9.5%
3 BEDROOM	960	5	5.3%
TOTAL		95	




OUTDOOR AMENITY		
TYPE	AREA m²	AREA ft²
RESIDENTIAL AMENITY (L6)	502.1	5,405
PUBLIC AMENITY COURTYARD (L1)	374.9	4,035
TOTAL	877.0	9,440


PRIVATE OUTDOOR SPACE		
TYPE	AREA m²	AREA ft²
PRIVATE RESIDENTIAL PATIOS	105.0	1,130
PRIVATE RESIDENTIAL BALCONIES	73.1	787
TOTAL	178.1	1,917


FLOORPLATE SIZES (L3-L6)		
TYPE	AREA m²	AREA ft²
RESIDENTIAL A (RENTABLE)	479.6	5,163
RESIDENTIAL A (M/E/CIRC)	67.4	726
TOTAL RES. A	547.1	5,888
RESIDENTIAL B (RENTABLE)	530.1	5,706
RESIDENTIAL B (M/E/CIRC)	72.3	779
TOTAL RES. B	602.5	6,485


STORAGE LOCKERS		
LOCATION	# OF RES UNITS	# OF LOCKERS
P1		46
Level 1		13
TOTAL LOCKERS	95	59
		62.1%


GARBAGE + RECYCLING ROOMS		
	LOCATION	AREA ft²
SHARED RES. + COMM.	LEVEL P1	440




















1 North - South Section 2
A2.01 SCALE: 1 : 100