



PROJECT DESCRIPTION

CIVIC ADDRESS:
1921, 1929, 1933 and 1935 ASHGROVE ST, 1900 RICHMOND RD

LEGAL DESCRIPTION:
 • PARCEL A (DD 82534) OF LOTS 39 AND 40 SECTION 76 VICTORIA DISTRICT PLAN 257
 • STRATA LOTS A AND B SECTION 76 VICTORIA DISTRICT STRATA PLAN VIS5007
 • PARCEL A (DD 411251) LOT 38 SECTION 76 VICTORIA DISTRICT PLAN 257
 • LOT 36 SECTION 76 VICTORIA DISTRICT PLAN 257

REGISTERED OWNER

Amica Oak Bay Inc.
3200-20 Queen Street
Toronto, ON
M5H 3R3
tel: 604-761-5939
email: drmilliken@millikendevelopments.com

ARCHITECT
de Hoog & Kierulf architects
977 Fort Street
Victoria, BC
V8V 3K3
Mr. Charles Kierulf Architect AIBC MRAIC
tel: 250-658-3367
fax: 250-658-3397
email: crk@dhk.ca

CIVIL ENGINEER
McElhanney
Suite 500, 3960 Quadra Street
Victoria BC
V8X 4A3
Mr. Colin Davis
tel: 250-370-9221
email: cdavis@mcelhanney.com


LANDSCAPE ARCHITECT
LADR
3-864 Queens Avenue
Victoria, B.C.
V8T 1M5
Mr. Chris Windjack
tel: 250-598-0105
email: cwindjack@ladr.ca

SITE INFORMATION BASED ON DRAWINGS PREPARED BY

Polaris Land Surveying
1834C Oak Bay Ave #138
Victoria, BC
V8R 0A4
File: 1332-06
Ms. Michelle Blake
tel: 250-412-3513

LIST OF DRAWINGS

Architectural
 A0.0 Cover Sheet
 A1.0 Project Data
 A1.1 ZONING DATA
 A2.0 Parkade Plan
 A2.1 Main Floor Plan
 A2.2 L2 to L4 Plan
 A2.3 L5 Plan
 A2.4 L6 PLAN
 A2.5 Roof Plan
 A3.0 Elevations
 A3.1 Street Context Elevations
 A3.2 Street Context Elevation (Birch)
 A3.3 Elevation Overlay PH1 on PH2
 A4.0 Building Sections
 A5.0 Model Views
 A5.1 Model Views
 A5.2 Model Views
 A5.3 Model Views
 A6.0 Shadow Study - Summer Solstice, Autumnal Equinox, Winter Solstice
 A7.0 Colour & Materials



Civil
22036-DP Conceptual Site Servicing Plan

Landscape
 L1 Landscape Concept Plan
 L2 Tree Management Plan

BUILDING CODE SUMMARY

REFERENCED DOCUMENT :
BRITISH COLUMBIA BUILDING CODE 2018 - PART 3

MAJOR OCCUPANCY CLASSIFICATION:
 • RESIDENTIAL - GROUP C
 • PARKADE - GROUP F3
 • EXISTING PH1 - GROUP B3


MAJOR OCCUPANCY FIRE SEPARATIONS:
 • C - B3 <-> F3 - 1 hr.

BUILDING AREA:
 • 1 135 m2 (PH2)



BUILDING HEIGHT:
 • 6 STOREYS

NUMBER OF STREETS FACING:
 • 1





1 Location Plan
 A0.1 1:500



3 Site Plan Data
 A0.1 1:200

PARKING CALCULATIONS
 REQUIRED PER SCHEDULE C

CLASS : ASSISTED LIVING FACILITY

PROJECT INFORMATION TABLE	PHASE 2	PHASE 1 EXISTING	COMBINED SITES
ZONE (EXISTING)	R3-2, R1-B, C1-R	C1-R	
PROPOSED ZONE			NEW ZONE
SITE AREA (M2)	2,769 m2	4,065 m2	6834.0 m2
TOTAL FLOOR AREA INCL COMMERCIAL (M2)	6,585 m2	10,771 m2	17,356 m2
COMMERCIAL FLOOR AREA (M2)		170 m2	170 m2
FLOOR SPACE RATIO	2.38	2.65	2.54
SITE COVERAGE (%)	48.6 %	54.4 %	53.3 %
OPEN SITE SPACE (%)	40.9 %	37.1 %	36.2 %
HEIGHT OF BUILDING (M)	26.58 m	20.6 m	26.58 m
NUMBER OF STOREYS	6	5	6
PARKING STALLS (NUMBER) ON SITE	55	47	101 (15 ACCESSIBLE)
BICYCLE PARKING NUMBER	CLASS 1 5	8	13
	CLASS 2 6	2	8

PHASE 2 - 88 SUITES
 PHASE 1 - 125 SUITES
 TOTAL - 213 SUITES

VEHICLES - 213 X 0.35 = 74.55
 VISITORS - 213 X 0.1 = 21.30
 RETAIL PH1 1 PER 50m2 = 3.40
 TOTAL = 99.25
 NEAREST WHOLE = 99 STALLS

BICYCLES
 LONG-TERM :
 213 @ 1 PER 20 = 10.65
 = 11


SHORT-TERM
 213 @ 1 PER 50 = 4.26
 = 4

BUILDING SETBACKS (M)	
STREET LOT LINE	7.05 m Project WEST
INTERIOR LOT LINE	5.63 m Project NORTH
INTERIOR LOT LINE	4.27 m Project SOUTH

RESIDENTIAL USE DETAILS	
TOTAL NUMBER OF UNITS	88
UNIT TYPE, E.G., 1 BEDROOM	Studio, 1-Bedroom, 1-Bedroom + Den, 2-Bedroom
GROUND-ORIENTATED UNITS	8
MINIMUM UNIT FLOOR AREA (M2)	43.4 m2
TOTAL RESIDENTIAL FLOOR AREA (M2)	5,165.9 m2

EV CHARGING:
 1 PER VEHICLE SPACE = 43 STALLS
 (PHASE 2 NEW CONSTRUCTION ONLY)

ACCESSIBLE PARKING :
 75 VEHICLES @ 15% = 11.25 = 11 R
 (9 REG + 2 VAN)
 21 VEHICLES @ 15% = 3.15 = 3 V
 (2 VISITOR AND 1 VISITOR VAN)
 TOTAL VEHICLE UA REQ'D = 11
 (9 REG + 2 VISITOR)
 TOTAL VAN UA REQ'D = 3
 (2 REG + 1 VISITOR)
 TOTAL REQUIRED = 14
 TOTAL PROVIDED = 15




2 Survey Plan
 A0.1 1:500

BUILDING AREA SUMMARY
 REFER TO A1.1 PLAN

AMICA SENIOR LIVING JUBILEE HOUSE - PHASE 2
 Project Data

RE-ISSUED FOR REZONING & DP : 26 JULY 2023





A1.0

	SITE COVERAGE INCL. BALCONIES GRADE OUTLINE 3,644.89 m ² 53.34%
	OPEN SITE SPACE 2,470.97 m ² 36.16%
	OTHER: DRIVEWAY, PARKING 675.92 m ² 9.90%
	SITE AREA 6,833.76 m ²


AVERAGE GRADE CALCULATION (in meters)					
GRADE POINT	DISTANCE	START	END	AVERAGE	TOTAL
A-B	7.85	24.42	24.40	24.41	191.62
B-C	0.89	24.40	24.38	24.39	21.71
C-D	10.69	24.38	24.06	24.22	258.91
D-E	0.64	24.06	24.02	24.04	15.39
E-F	28.14	24.02	23.90	23.96	674.23
F-G	0.64	23.90	23.94	23.92	15.31
G-H	10.69	23.94	23.86	23.90	255.49
H-J	0.89	23.86	23.90	23.88	21.25
J-K	7.85	23.90	23.78	23.84	187.14
K-L	15.67	23.78	23.72	23.75	372.16
L-M	2.26	23.72	23.72	23.72	53.61
M-N	6.50	23.72	23.58	23.65	153.73
N-P	32.90	23.58	23.72	23.65	778.09
P-Q	7.87	23.72	23.25	23.49	184.83
Q-R	7.64	23.25	23.12	23.19	177.13
R-S	44.45	23.12	23.12	23.12	1,027.68
S-T	17.22	23.12	23.12	23.12	398.13
U-V	5.42	22.75	22.75	22.75	123.31
V-W	6.96	22.75	23.12	22.94	159.63
W-X	40.19	23.12	23.12	23.12	929.19
X-Y	25.16	23.12	23.12	23.12	581.70
Y-Z	29.92	23.12	23.12	23.12	691.75
Z-AA	21.69	23.12	23.12	23.12	501.47
AA-BB	37.12	23.12	23.12	23.12	858.21
BB-CC	20.59	23.12	23.12	23.12	476.04
CC-DD	7.65	23.12	23.35	23.24	177.75
DD-EE	7.86	23.25	23.75	23.50	184.71
EE-FF	22.93	23.75	23.75	23.75	544.59
FF-GG	6.50	23.72	23.92	23.82	154.83
GG-HH	2.26	23.92	23.94	23.93	54.08
HH-A	15.67	23.94	24.42	24.18	378.90
TOTAL	452.71			10,602.57	

AVERAGE GRADE 23.42


TOTAL FLOOR AREA CALC.		
PHASE 2 BUILDING		
LEVEL 1	860	m ²
ST-1	20	m ²
WALKWAY LINK	75	m ²
LEVEL 2	1 135	m ²
LEVEL 3	1 135	m ²
LEVEL 4	1 135	m ²
LEVEL 5	1 115	m ²
LEVEL 6	1 075	m ²
ROOFTOP	35	m ²
TOTAL PHASE 2	6 585	m²




Revisions
 Received Date: August 17, 2023
 Deemed Date: July 28, 2023



A1.1




Revisions
 Received Date: August 17, 2023
 Deemed Date: July 12, 2023




ASHGROVE ST


FORT ST




Revisions
 Received Date: August 17, 2023
 Deemed Date: July 12, 2023




A2.1





AMICA SENIOR LIVING JUBILEE HOUSE - PHASE 2
L2 to L4 Plan

RE-ISSUED FOR REZONING & DP : 11 JULY 2023



SENIORS MEMORY CARE
29 SUITES


PHASE 1 BUILDING
(see BP056068)

BALCONY

BALCONY
1637 sf




BALCONY

PARKAI
RAMF



AMICA SENIOR LIVING JUBILEE HOUSE - PHASE 2
L6 Plan

RE-ISSUED FOR REZONING & DP : 11 JULY 2023




PROPERTY LINE

EXISTING BUILDING ROOF OUTLINE

EXISTING BUILDING

31.93



PHASE 1 BUILDING
(see BP056068)

RICHMOND RD

BIRCH ST


PROJECT NORTH





WEST ELEVATION


- MATERIALS KEY :
1. Cementitious Panel Siding - various colours - with colour-matched trims.
 2. Aluminum and Glass guard.
 3. High-Performance Vinyl windows with coloured frames.
 4. High-Performance aluminum and glass window-wall system.
 5. Metal siding with printed wood grain pattern.
 6. Smooth face masonry cladding.
 7. Prefinished metal cladding.
 8. Rooftop solar PV array.
 9. Rooftop amenity area with planters.
 10. Concrete column.
 11. Steel and glass canopy.
 12. Rooftop beekeeping hives.
 13. Louvre Screen Wall



SOUTH ELEVATION



EAST ELEVATION



NORTH ELEVATION





1760 Fort

1914

1918

1922

1928

1934-1936

1944

STREET CONTEXT ELEVATION - ASHGROVE STREET LOOKING WEST



STREET CONTEXT ELEVATION - ASHGROVE STREET LOOKING EAST





Street Context Elevation - Birch Street - Phase 2 in background
(Phase 1 and context masked 60%)







EAST ELEVATION WITH PHASE 1 WINDOW OPENINGS OVERLAID

AMICA SENIOR LIVING JUBILEE HOUSE - PHASE 2
Elevation OVERLAY PH1 WINDOWS on PH2

RE-ISSUED FOR REZONING & DP : 11 JULY 2023



SECTION WEST - EAST



SECTION SOUTH - NORTH

AMICA SENIOR LIVING JUBILEE HOUSE - PHASE 2
Building Sections

RE-ISSUED FOR REZONING & DP : 11 JULY 2023





Aerial View - Looking West from Richmond Road
Phase 1 in Foreground



Aerial View - Looking South West from Richmond Road
Phase 1 in Foreground



Aerial View - Looking South East from Ashgrove Street
Phase 1 in Background





Street View - Looking North from Richmond Street

Phase 1 on the right ; Commercial Buildings in the foreground on Fort Street






Street View - Looking South along Ashgrove Street






Aerial View - Looking East over Fort Street with RJH Buildings in Background







JUNE 21 - 08:00




JUNE 21 - 11:00




JUNE 21 - 14:00




JUNE 21 - 17:00




SEPTEMBER 23 - 09:00




SEPTEMBER 23 - 11:00




SEPTEMBER 23 - 13:00




SEPTEMBER 23 - 15:00




DECEMBER 21 - 10:00



DECEMBER 21 - 11:00



DECEMBER 21 - 12:00



DECEMBER 21 - 13:00




Vertical Louver Screen Wall
North and South Elevations




High-Performance aluminium and
glass window-wall system



Rooftop solar PV array



Rooftop amenity area with planters




Cementitious Panel Siding- Various colours-
with colour matching trims



Rooftop beekeeping hives




High-Performance vinyl windows with coloured
frames




WEST ELEVATION




Prefinished metal cladding




Aluminium and Glass guard



Metal Siding (inside face of vertical fins) and all Soffits
with printed wood grain finish



Steel and glass canopy



Smooth face masonry cladding

DATE: 2023-02-22 22:17 FILE: X:\2241\Civil\Projects\2241-22036-00\Amica Oak Bay - Phase 2\10.0 DRAWINGS\10.3 Engineering\10.3.2 Sheets\22036-00-ALL.dwg McElhanney ANS D - 2021-12-08

Revisions
 Received Date: July 26, 2023
 Deemed Date: July 12, 2023

CONSTRUCTION NOTES


- ① EXISTING WATER SERVICE TO BE CAPPED AND ABANDONED BY CoV FORCES AT DEVELOPER'S EXPENSE
- ② EXISTING SANITARY SEWER SERVICE TO BE CAPPED AND ABANDONED BY CoV FORCES AT DEVELOPER'S EXPENSE
- ③ EXISTING STORM SEWER SERVICE TO BE CAPPED AND ABANDONED BY CoV FORCES AT DEVELOPER'S EXPENSE
- ④ NEW xØ DOMESTIC WATER SERVICE CONNECTION c/w xØ WATER METER AND 150Ø FIRE WATER SERVICE CONNECTION c/w CHECK VALVE BY CoV FORCES AT DEVELOPER'S EXPENSE PER CoV STD. DWG. SDW2h.
- ⑤ NEW xxØ STORM SERVICE AND xxØ NEW SANITARY SERVICE IN COMMON TRENCH BY CoV FORCES AT DEVELOPER'S EXPENSE PER MMCD STD. DWG. S7 c/w INSPECTION CHAMBER AT PROPERTY LINE. INSPECTION CHAMBER PER MMCD STD. DWG. S9 c/w CONCRETE BOX AND CAST IRON LID.
- ⑥ NEW FIRE HYDRANT BY CoV FORCES AT DEVELOPER'S EXPENSE
- ⑦ EXISTING CATCHBASIN TO BE ADJUSTED TO SUIT NEW CURB AND GUTTER. MAINTAIN EXISTING LEAD.
- ⑧ NEW DRIVEWAY PER CoV STD. DWG. SDC7b WITH WIDTHS AS NOTED ON PLAN
- ⑨ EXISTING GAS SERVICE TO BE CAPPED AND ABANDONED BY FORTISBC FORCES AT DEVELOPER'S EXPENSE

LEGEND

- NEW ROAD CONSTRUCTION
 - 80mm ACP (2 LIFTS)
 - 150mm BASE COURSE
 - 200mm SUBBASE COURSE
- NEW CONCRETE SIDEWALK
- NEW SOD BOULEVARD

SHEET NOTES:

1. FOR PROPOSED BUILDING AND ONSITE DESIGN INFORMATION, SEE DRAWINGS BY JHK ARCHITECTS.
2. EXISTING TOPOGRAPHIC SURVEY SHOWN WAS PROVIDED BY POLARIS LAND SURVEYING INC.
3. UTILITY SERVICE SIZES AND LOCATIONS TO BE DETERMINED DURING DETAILED DESIGN.
4. EXISTING ON-SITE BUILDINGS, DRIVEWAYS, PAVED AREAS, FENCES ETC. TO BE REMOVED ARE NOT SHOWN FOR CLARITY.
5. ALL OFFSITE TREES NOT NOTED FOR REMOVAL TO BE PROTECTED DURING CONSTRUCTION UNLESS OTHERWISE DETERMINED BY PROJECT ARBORIST DURING DETAILED DESIGN.
6. SEE TREE MANAGEMENT PLAN BY TALBOT MACKENZIE FOR TREE PROTECTION DETAILS AND FOR ONSITE TREE REMOVALS




Rev	Date	Description	Drawn	Design	App'd
1	2023-02-22	REVISED FOR DP / REZONING	GP	CD	CD
0	2022-12-09	ISSUED FOR DP / REZONING	GP	CD	CD

THIS DRAWING AND DESIGN IS THE PROPERTY OF McELHANNEY AND SHALL NOT BE USED, REUSED OR REPRODUCED WITHOUT THE CONSENT OF McELHANNEY. McELHANNEY WILL NOT BE HELD RESPONSIBLE FOR THE IMPROPER OR UNAUTHORIZED USE OF THIS DRAWING AND DESIGN.

THIS DRAWING AND DESIGN HAS BEEN PREPARED FOR THE CLIENT IDENTIFIED, TO MEET THE STANDARDS AND REQUIREMENTS OF THE APPLICABLE PUBLIC AGENCIES AT THE TIME OF PREPARATION. McELHANNEY, ITS EMPLOYEES, SUBCONSULTANTS AND AGENTS WILL NOT BE LIABLE FOR ANY LOSSES OR OTHER CONSEQUENCES RESULTING FROM THE USE OR RELIANCE UPON, OR ANY CHANGES MADE TO, THIS DRAWING, BY ANY THIRD PARTY, INCLUDING CONTRACTORS, SUPPLIERS, CONSULTANTS AND STAKEHOLDERS, OR THEIR EMPLOYEES OR AGENTS, WITHOUT McELHANNEY'S PRIOR WRITTEN CONSENT.

INFORMATION ON EXISTING UNDERGROUND FACILITIES MAY NOT BE COMPLETE OR ACCURATE. McELHANNEY, ITS EMPLOYEES AND DIRECTORS ARE NOT RESPONSIBLE NOR LIABLE FOR THE LOCATION OF ANY UNDERGROUND CONDUITS, PIPES, CABLES OR OTHER FACILITIES WHETHER SHOWN OR OMITTED FROM THIS PLAN. PRIOR TO CONSTRUCTION CONTRACTOR SHALL EXPOSE LOCATIONS OF ALL EXISTING FACILITIES BY HAND DIGGING OR HYDROVAC AND ADVISE THE ENGINEER OF POTENTIAL CONFLICTS.



ORIGINAL DWG SIZE: ANSI D (22" x 34")

McElhanney

Suite 500
 3960 Quadra Street
 Victoria BC
 Canada V8X 4A3
 T 250 370 9221

**PRELIMINARY
 NOT FOR
 CONSTRUCTION**


THIS DRAWING HAS NOT BEEN APPROVED AND MAY CONTAIN ERRORS AND OMISSIONS

MILLIKEN DEVELOPMENTS
 #100-2489 BELLEVUE AVENUE, WEST VANCOUVER, BC V7V 1E1

**AMICA JUBILEE HOUSE PHASE 2
 CONCEPTUAL SITE SERVICING PLAN**

Drawing No.	22036-DP
Project Number	2241-22036-00
Rev.	1


DESTROY ALL PRINTS BEARING PREVIOUS REVISION



Recommended Nursery Stock

Trees	Quantity	Botanical Name	Common Name	Size
	3	Alnus rubra (Lrg / 1:1)	Red Alder	6cm cal.
	1	Boulevard Street Tree	Species to be determined	6cm cal.
	9	Cercidiphyllum japonicum (Med. / 1:1)	Katsura Tree	6cm cal.
	5	Cercis canadensis (Med. / 1:1)	Eastern Redbud	6cm cal.
	2	Cornus x 'Venus' (1:1 Structure)	Venus Cornus	4cm cal.
	2	Malus domestica 'Jonagold' (Sm. / 2:1)	Semi-Dwarf Apple	6cm cal.
	1	Stewartia pseudocamellia (Sm. / 2:1)	Japanese Stewartia	6cm cal.
Large Shrubs				
Total:	72			
		Botanical Name	Common Name	Size
		Ceanothus thyrsiflorus 'Victoria'	Victoria Ceanothus (California Lilac)	#5 pot
		Choisya ternata	Mexican Orange Blossom	#5 pot
		Cornus sericea 'Flaviramea'	Midwinter Fire Dogwood	#5 pot
		Oemleria cerasiformis	Indian Plum	#5 pot
		Philadelphus lewisii	Mock Orange	#5 pot
		Pieris 'Forest Flame'	Forest Flame Pieris	#5 pot
		Vaccinium ovatum	Evergreen Huckleberry	#5 pot
Medium Shrubs				
Total:	150			
		Botanical Name	Common Name	Size
		Hydrangea macrophylla 'Lanarth White'	Lanarth White Hydrangea	#5 pot
		Mahonia aquifolium	Tall Oregon Grape	#5 pot
		Rhododendron 'Fantastica'	Fantastica Rhododendron	#5 pot
		Rhododendron macrophyllum	Pacific Rhododendron	#5 pot
		Ribes sanguineum	Red Flowering Currant	#5 pot
		Symphoricarpos albus	Snowberry	#5 pot
Small Shrubs				
Total:	561			
		Botanical Name	Common Name	Size
		Azalea japonica 'Herbert'	Herbert Evergreen Azalea	#1 pot
		Azalea 'Snowbird'	Snowbird Azalea	#1 pot
		Berberis thunbergii f. atropurpurea 'Bagatelle'	Dwf Purpleleaf Japanese Barberry	#1 pot
		Ceanothus 'Blue Sapphire'	Blue Sapphire Ceanothus	#1 pot
		Cistus x argenteus 'Silver Pink'	Silver Pink Rock Rose	#1 pot
		Cornus stolonifera 'Kelsey'	Kelsey Dogwood	#1 pot
		Gaultheria shallon	Salal	#1 pot
		Hebe odora 'New Zealand Gold'	New Zealand Hebe	#1 pot
		Hydrangea macrophylla 'Lanarth White'	Lanarth White Hydrangea	#5 pot
		Lavandula angustifolia 'Munstead'	Munstead English Lavender	#1 pot
		Lavender stoechas 'Anoluk'	Anouk Spanish Lavender	#1 pot
		Mahonia nervosa	Low Oregon Grape	#1 pot
		Nandina domestica 'Wood's Dwarf'	Wood's Dwarf Heavenly Bamboo	#1 pot
		Sarcococca hookeriana var. humilis	Dwarf Sweet Box	#1 pot
Perennials, Annuals and Ferns				
Total:	207			
		Botanical Name	Common Name	Size
		Calamagrostis x acutiflora 'Karl Foerster'	Karl Foerster Feather Reed Grass	#1 pot
		Festuca idahoensis	Idaho Fescue	#1 pot
		Helictotrichon sempervirens	Blue Oat Grass	#1 pot
		Perovskia atriplicifolia	Russian Sage	#1 pot
		Phormium tenax 'Tiny Tiger'	Dwarf Variegated New Zealand Flax	#1 pot
		Polystichum munilum	Sword Fern	#1 pot
		Stipa tenuissima	Mexican Feather Grass	#1 pot

Notes:
 1. All work to be completed to current CSLA Landscape Standards
 2. All soft landscape to be irrigated with an automatic irrigation system




1 Landscape Concept Plan
Scale: 1:125

1:125
 Revision F | Issued for DP ReSubmission I June 8/23
 Revision E | Issued for DP ReSubmission I Apr. 11/23
 Revision D | Issued for Draft DP ReSubmission I Feb. 24/23
 Revision C | Issued for Draft DP Submission I Dec. 15/22
 Revision B | Issued for Coordination I Dec. 7/22
 Revision A | Issued for Rezoning I Sept. 16/22

Landscape Concept Plan - Jubilee House Phase 2

ASHGROVE STREET



Tree Inventory Table

Tag #	Location	Species	Caliper	DBH	Height	Condition	Remarks	Retention	Removal
051	City	Yes	Cherry	21	15	3	Good	Y	Y
052	No	Off	Yes	Cherry	37	8	4.2	3	Fair
053	Yes	On	Yes	Cherry	37	8	4.4	3	Fair
054	Yes	On	Yes	Cherry	37	8	4.2	3	Fair
055	Yes	On	Yes	Cherry	37	8	4.2	3	Fair
056	Yes	On	Yes	Cherry	37	8	4.2	3	Fair
057	Yes	On	Yes	Cherry	37	8	4.2	3	Fair
058	Yes	On	Yes	Cherry	37	8	4.2	3	Fair
059	Yes	On	Yes	Cherry	37	8	4.2	3	Fair
060	Yes	On	Yes	Cherry	37	8	4.2	3	Fair
061	Yes	On	Yes	Cherry	37	8	4.2	3	Fair
062	Yes	On	Yes	Cherry	37	8	4.2	3	Fair
063	Yes	On	Yes	Cherry	37	8	4.2	3	Fair
064	Yes	On	Yes	Cherry	37	8	4.2	3	Fair
065	Yes	On	Yes	Cherry	37	8	4.2	3	Fair
066	Yes	On	Yes	Cherry	37	8	4.2	3	Fair
067	Yes	On	Yes	Cherry	37	8	4.2	3	Fair
068	Yes	On	Yes	Cherry	37	8	4.2	3	Fair
069	Yes	On	Yes	Cherry	37	8	4.2	3	Fair
070	Yes	On	Yes	Cherry	37	8	4.2	3	Fair
071	Yes	On	Yes	Cherry	37	8	4.2	3	Fair
072	Yes	On	Yes	Cherry	37	8	4.2	3	Fair
073	Yes	On	Yes	Cherry	37	8	4.2	3	Fair
074	Yes	On	Yes	Cherry	37	8	4.2	3	Fair
075	Yes	On	Yes	Cherry	37	8	4.2	3	Fair
076	Yes	On	Yes	Cherry	37	8	4.2	3	Fair
077	Yes	On	Yes	Cherry	37	8	4.2	3	Fair
078	Yes	On	Yes	Cherry	37	8	4.2	3	Fair
079	Yes	On	Yes	Cherry	37	8	4.2	3	Fair
080	Yes	On	Yes	Cherry	37	8	4.2	3	Fair
081	Yes	On	Yes	Cherry	37	8	4.2	3	Fair
082	Yes	On	Yes	Cherry	37	8	4.2	3	Fair
083	Yes	On	Yes	Cherry	37	8	4.2	3	Fair
084	Yes	On	Yes	Cherry	37	8	4.2	3	Fair
085	Yes	On	Yes	Cherry	37	8	4.2	3	Fair
086	Yes	On	Yes	Cherry	37	8	4.2	3	Fair
087	Yes	On	Yes	Cherry	37	8	4.2	3	Fair
088	Yes	On	Yes	Cherry	37	8	4.2	3	Fair
089	Yes	On	Yes	Cherry	37	8	4.2	3	Fair
090	Yes	On	Yes	Cherry	37	8	4.2	3	Fair
091	Yes	On	Yes	Cherry	37	8	4.2	3	Fair
092	Yes	On	Yes	Cherry	37	8	4.2	3	Fair
093	Yes	On	Yes	Cherry	37	8	4.2	3	Fair
094	Yes	On	Yes	Cherry	37	8	4.2	3	Fair
095	Yes	On	Yes	Cherry	37	8	4.2	3	Fair
096	Yes	On	Yes	Cherry	37	8	4.2	3	Fair
097	Yes	On	Yes	Cherry	37	8	4.2	3	Fair
098	Yes	On	Yes	Cherry	37	8	4.2	3	Fair
099	Yes	On	Yes	Cherry	37	8	4.2	3	Fair
100	Yes	On	Yes	Cherry	37	8	4.2	3	Fair

Tree Preservation Summary

Category	Count	Multipplier	Total
A. Protected Trees Removed	18	X 1	18
B. Replacement Trees Proposed per Schedule "E", Part 1	19	X 1	19
C. Replacement Trees Proposed per Schedule "E", Part 2	3*	X 0.5	1.5*
D. Replacement Trees Proposed per Schedule "E", Part 3	16*	X 1	16*
E. Total replacement trees proposed (B+C+D) Round down to nearest whole number	35		35
F. Onsite replacement tree deficit (A-E) Record 0 if negative number	0		0
G. Tree minimum on lot	14		14
H. Protected trees retained (other than specimen trees)	0	X 1	0
I. Specimen trees retained	0	X 3	0
J. Trees per lot deficit (G - (H+I)) Record 0 if negative number	0		0
K. Protected trees Removed	0	X 1	0
L. Replacement trees proposed per Schedule "E", Part 1 or Part 2	0	X 1	0
M. Replacement trees proposed from Schedule "E", Part 2	0	X 0.5	0
N. Total replacement trees proposed (L+M) Round down to nearest whole number	0		0
O. Offsite replacement tree deficit (K - N) Record 0 if negative number	0		0
P. Onsite trees proposed for cash-in-lieu Enter F, or J, whichever is the greater number	0		0
Q. Offsite trees proposed for cash-in-lieu Enter O	0		0
R. Cash-in-lieu proposed ((P+Q) X \$2,000)	0		\$0


Soil Volume Compliance Table

Planting Area (ID)	Area (m2)	Soil Volume (m)	Est. Soil Volume	Replacement Trees Proposed				Soil Volume Required (m3)			Compliance (Y / N)
				B Small	C Medium	D Large	E # Small	F # Medium	G # Large	Total	
1	169	0.75	126.75	0.0	1.0	0.0	0.0	20.0	0.0	20.0	Y
2	360	0.75	270	2.0	6.0	2.0	16.0	120.0	70.0	206.0	Y
3	75	0.75	56.25	0.0	1.0	0.0	0.0	20.0	0.0	20.0	Y
4	70	0.75	52.5	0.0	2.0	0.0	0.0	40.0	0.0	40.0	Y
5	129	0.75	96.75	0.0	4.0	0.0	0.0	80.0	0.0	80.0	Y
6	14.2	0.75	10.65	1.0	0.0	0.0	8.0	0.0	0.0	8.0	Y
7	12.5	1	12.5	2.0	0.0	0.0	12.0	0.0	0.0	12.0	Y
8	33	0.75	24.75	0.0	1.0	0.0	0.0	20.0	0.0	20.0	Y
TOTAL			650.15					406.0			

Tree Impact Summary Table

Tree Status	A Total # of Protected Trees	B # of Trees to be REMOVED	C # of NEW or REPLACEMENT Trees to be Planted*	D # of EXISTING non-protected Trees Counted as Replacements
Onsite Trees	18	18	22*	0
Private Offsite Trees	2	0	N/A	N/A
Municipal Trees	5	2	N/A	N/A
Total	25	20	22*	0

Existing Trees Legend:



1 Landscape Tree Management Plan Scale: 1:125

1:125

Tree Management Plan - Jubilee House Phase 2



Project No: 2214 13 May 2022 #3-864 Queens Ave. Victoria B.C. V8T1M5 Phone: (250) 598-0105

Revision F | Issued for DP ReSubmission I June 8/23
 Revision E | Issued for DP ReSubmission I Apr. 11/23
 Revision D | Issued for Draft DP ReSubmission I Feb. 24/22
 Revision B | Issued for Coordination I Dec. 19/22
 Revision A | Issued for Rezoning I Sept. 16/22